

Mechanical Issues and Recent Progress on the CRT Stand Design

K. Suzuki (Nagoya)

Revised on 7/29/2012

Introduction (1)

- *Originally the CRT data taking was planned to start at the beginning of September.*
 - *Using newly produced IRS2 daughter cards.*
 - *Having some improvements on cooling, HV divider and PMT sockets with alignment mechanism.*
- *Given the status, the highest priority is to get the proof of principle for the optics ASAP.*
 - *That is, for now, the improvement on the β -resolution given by the full PMT-coverage to the radiator end.*
 - *The improvement from the half-coverage to the full-coverage has been seen in Arita's MC study (See, Inami-san's talk in the BPID session).*
 - *We need to confirm it in data.*
 - *The strategy is to have a beam test on the LEPS beam line at SPring-8, using the FNAL prototype radiator and mirror and the CFD-readout modules ("LEPS prototype").*
 - *The LEPS beam will be available in Oct. 2nd – 9th.*
 - *No expansion block this time due to the shortage of financial/man-power resources to produce front/back-end modules.*


Introduction (2)

- *By the Oct. beam test, we need to prepare the readout system and to have operational tests and a cosmic-ray test for the “LEPS prototype”.*
 - *The CFD-readout modules for 16ch. SL10 are supposed to be ready for use by the end of August.*
 - *As well as associated structures/jigs and back-end modules.*
 - *The results of the tests are important for the Focused Review (Oct. 1st – 2nd) to show some progress in the right direction.*

CRT assembly schedule – option A – (1)

- My proposal of the CRT assembly schedule (“option A”) is shown below.

Schedule Option A




CRT assembly schedule – option A – (2)

- *Hence, the CRT stand and Strong Back need to be ready for use by the beginning of September.*
 - *Considering the “Obon-break” (Aug. 13th – 15th) and the KEK power outage (Aug. 16th – 18th).*
- *Given the tight schedule, the existing design should be realized ASAP, taking into account possible extensions and modifications.*
 - *The existing design is based on Gary Varner’s proposal and is modified/drawn by Marc Rosen.*
 - *Extensions/modifications should be applied time to time.*
 - *What are the mechanical issues for realization?*


Issues on the CRT design

- *Need to decide the followings.*
 - *Dimensions and “shelf”-spacing,*
 - *What is the baseline config.? Possible extensions?*
 - *Assembly method,*
 - *Where/how/how many people to assemble?*
Need a crane during the assembly? Where to anchor? How to secure the range stack?
 - *Operation scheme.*
 - *How to install a module? How many incident positions to take? Use IP-assumed tracks?*
- *Need to evaluate the followings.*
 - *Sag of a counter module with the Strong Backs attached,*
 - *Sag of the beams of the CRT stand with counter modules installed,*
 - *Seismic performance assessment,*
 - *1G for vertical load, 0.25G for lateral load.*
 - *Natural frequency.*
 - *Cost.*

Flat beams: 2989mm long x 250mm high x 20mm thick, modeled in structural steel, Ti, and Al. using COMSOL Multiphysics 4.2.





“Strong Back” by Marc Rosen



CRT stand by Marc Rosen

Dimensions and spacing


- *Dimensions and “shelf”-spacing.*
 - *Baseline: SciFi trackers, timing counters, TOF trig. counters and a range stack.*
 - *Extension: cherenkov counters for further β -selection?, a movable range stack?*
 - *Where/how to mount them? How much spaces do they need?*
 - *See Matt Barrett’s talk and Jim Fast’s talk in this session.*
- *Accumulation of small space-savings would help to lower the height or to make more spaces.*
 - *For safety (seismic proof), module installation and possible CRT extensions.*
 - *Al-beams: $100 \times 200 \text{ mm}^2 \rightarrow (50-100) \times 100 \text{ mm}^2$?*
 - *D: 700 mm \rightarrow D: 600 mm?*
 - *More steep slope for the buttresses?*
 - *Lead, instead of iron, for the range stack?*



Layout plan for the Tent House (660 x 880 cm²): ver. 2012/07/04


Lower-roof section (640 x 360 x H~250 cm³)

Higher-roof section (640 x 490 x H~500 cm³)




Lead for the range stack (1)

- Especially, a smaller height and more vertical spacing would be desirable for the CRT stand.
 - $H < 5.2 \text{ m}$ (phys. limit).
 - 0.5-1 m clearance at the top (safety+work)?
 - 16 cm for timing counters (4 cm x 4 layers).



12.7.23



- Use lead for the range stack.
 - Suggested by Alan Schwartz.
 - The height can be 1/3 of iron.

Material	λ_T [g/cm ²]	λ_I [g/cm ²]	X_0 [g/cm ²]	$dE/dx _{min}$ [MeV·cm ² /g]	ρ [g/cm ³]	X_0/ρ [cm]
Fe	81.7	132.1	13.84	1.451	7.874	1.76
Pb	114.1	199.6	6.37	1.122	11.350	0.56
Pb/Fe	1.40	1.51	0.46	0.77	1.44	0.32

BPID extra session @ B2GM12


Lead for the range stack (1)'

- *Made a mistake to evaluate the range stack height.*
 - *Particle of interest is μ , not e .*
 - *We should have looked at the energy loss (dE/dx), not the radiation length (X_0).*
 - *Resulting height reduction in Pb to Fe is only 11%.*
 - *No significant advantage to use lead instead of iron.*

<i>Material</i>	λ_T [g/cm ²]	λ_I [g/cm ²]	X_0 [g/cm ²]	$dE/dx _{min}$ [MeV*cm ² /g]	ρ [g/cm ³]	$dE/dx*\rho$ [MeV/cm]
<i>Fe</i>	81.7	132.1	13.84	1.451	7.874	11.425
<i>Pb</i>	114.1	199.6	6.37	1.122	11.350	12.735
<i>Pb/Fe</i>	1.40	1.51	0.46	0.77	1.44	1.11

Lead for the range stack (2)

- Hayashi-san kindly offered to use the lead stored in the Belle Tent.
 - Lead sheet ($100 \times 110 \times \sim 23 \text{ cm}^3$)
 - Lead wool (25 kg x 8 boxes)
- Adachi-san is kindly trying to get more lead for us.
 - There are many lead bricks at East Counter Hall, but they belong to the J-PARC division. Can we use them?
 - Anything else?



12-7-23

BPiD extra session @ B2GM12


イドレール 3509 重量用

- (1)
-
- ive.
- lide
- Fork-lift pockets
- スライドレール 3509 重量用
-
- ng
- l in

[illegible]

Operation scheme (2)

- A movable range stack
 - It would be difficult to have full-coverage of the range stack over the quartz optics (~ 2.7 m).
 - Not easy to handle/secure such a massive range stack.
 - Even unnecessary. What is the required coverage, i.e. planned incident positions, then?
 - Inami-san suggested to use IP-assumed tracks.
 - What are “incident positions” within the acceptance?
 - Should a single module go through all the shelves?
 - Do we not need to move the range stack at all, then?
 - If we want the range stack be movable, use of pair of linear guides seems to work.
 - Suggested by Toshi Kawai (Nagoya engineering group) based on his experience with telescope construction.
 - Need an iron plate (~ 10 mm) under the linear guides to bolt them; the CRT stand can be anchored through the plate.
 - Need an iron plate (~ 20 mm) on top of the linear guide blocks to place the lead/iron.
 - A hand-winch works to move; a horizontal resistance can be a few percent of the vertical load.





THK SHW35CA:

- ~ 150 k yen/guide for 3m length.
- ~ 1 month to deliver.


Mechanical performance assessment

- *Sag of the Strong Back*
 - *Marc Rosen evaluated the sag using FEM.*
 - *A preliminary result indicates acceptable sag ($\sim 45\ \mu\text{m}$) sag for Al Strong Back ($L2989 \times H250 \times T20\ \text{mm}^3$).*
 - *Need to incorporate more details.*
 - *Can we make the Strong Back smaller to reduce its weight and the vertical clearance in the CRT stand?*
 - *What about possible moments given by the installation scheme?*
- *Sag/seismic performance of the CRT stand.*
 - *Jim Fast and a PNNL engineer evaluated using FEM.*
 - *See Jim's talk in this session.*




Consideration on the Sep. CRT test


- To be used for the operational and CRT tests of the “LEPS prototype”.
 - Less than 1 month running.
 - Need enough operational tests for the Oct. beam test.
 - For the Focused Review, even with a certain period CRT running, N_{hit} would be only the material to be presented.
 - β -selection would not be good enough to deliver a meaningful β -resolution.
- Realizing the above items ~~and using the lead sheets~~, we can build a simple CRT stand dedicated for the Sep. runs.
 - Suggested Hayakawa-san.
 - See Hayakawa-san’s/Iijima-san’s talk in this session for more details.




Further simplification of the CRT stand (1)






- The range stack can be L100 x W100 x H~75 cm³.
 - Using all the iron blocks and the lead sheets. (2 block for shim-up)
 - ~~Corresponding to H1.25 m of the iron range stack.~~
- We need to make an “Al-base”.
 - Quick to assemble.
 - Easy access to a counter module.
 - Would cost ~50k yen.



Further simplification of the CRT stand (2)




- *The sheets, blocks and Al-base can be tied together using eye-bolts and wires.*
 - *There are threaded holes at the top and one side of the iron blocks.*
- *We can use 6 more iron blocks.*
 - *Each is L100 x W50 x H50 cm³.*
 - *Adachi-san kindly keeps them at the North Counter Hall.*
 - *Need experts' comments on how high the range stack can be for such a simple bench.*



CRT assembly schedule – option B –

- My proposal of the CRT assembly schedule (“option B”) is shown below.

Schedule Option B



- Extension of designing is only ~1 month.

- We should realize the design in Oct.

- Preproduction bars will be delivered in Dec.

- Next LEPS beam test may happen in Dec.

Summary

- *There are progresses on the CRT stand design.*
 - *Especially many people got involved seriously.*
 - *We should keep the activity level.*
- *There are, however, still various parameters, assembly method and operation scheme.*
 - *Need inputs form MC studies.*
 - *Need to discuss the possible conditions, e.g. incident positions, to take CR data.*
 - *Need to decide the base line configuration and possible extensions on the CRT test bench.*
 - *Iterate designing examining using FEM.*
- *Having a simple, temporary CRT bench can be considered for the Sep. CRT runs.*
 - *Giving ~1 month to finalize the CRT stand design based on careful considerations/discussions on the long-term CRT tests.*